EXECUTIVE ENGINEER'S OFFICE, MYSORE RAILWAYS, HASSAN.

Notification, dated 21st August 1933.

Notice is hereby given that the sealed tenders will be received at the Office of the Executive Engineer, Mysore Railways, Hassan, on any working day up to 2 P.M. on 11th September 1933, for Improvements to the Traffic Quarters on Tarikere-Narasimharajpura Tramway. An approximate estimate of quantities is given in the following schedule The quantities are not guaranteed. The work should be completed by the end of March 1934, showing continuous equal monthly progress.

2. Detailed estimates and plans and conditions of schedule agreement, may be seen at the Executive Engineer's Office at Mysore Railways, Hassan, on all working days, between 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer on payment of one rupee.

4. Every tender must be accompanied by a deposit of Rs. 100 in cash as earnest money and should be superscribed "Tenders for improvements to the Traffic Quarters on Tarikere-Narasimharajpura Tramway," in default of which, tenders will be rejected.

5. The earnest money of rejected tenders will be returned as early as possible after the tenders are disposed of and in the case of accepted tender it would be held as a part of security under clause 4 of Schedule of Agreement referred to.

6. The final acceptance of any tender will rest with the Superintendent, Way and Works, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender or any portion of a tender.

7. The name of the competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office. No enquiries regarding the acceptance or rejection of a tender will be answered.

8. Within eight days of the acceptance of the tender, the successful competitor is required to execute the usual schedule agreement, in default of which, his tender will be considered as cancelled.

9. Definite rates against each item of work in the Schedule should be noted both in figures and in words.

10. In case the accepted tenderer quarries stone, earth, kankar, sand, etc., from Government or Forest land for use on this work, Royalty at the rates fixed by the Government will be recovered from his bills.

SCHEDULE.

Items of work	Unit	Traffic quarters at Agasanahallu.	Traffic quarters at Narasimharajapura	Traffic quarters at Tadasa	Menials quarters at Tadasa	Menials quarters at Narasimharajapura	Menials quarters at Duggalapura	Total quantity
1. Dismantling the wall, removing the door and refixing the same complete.	Each	2	...	1	...	...	...	3
2. Do do window.	„	2	...	1	...	...	...	2
3. Earthwork excavation for foundation and refilling the same with soil.	1,000 C.ft.	160	230	250	144	534	303	1,621
4. Concrete broken stone jelly in mortar.	100 C.ft.	12	5	...	14	400	180	611
5. Burnt brick in mortar ...	„	303	463	410	220	250	184	1,830
6. Burnt brick in prepared clay.	„	322	482	470	300	1,223	518	3,315
7. Burnt stone slabs 6" thick roughly dressed including fixing.	S.ft.	107	81	71	26	61	21	367
8. Fixing charges for 41½ lb. rails for ridge, etc.	R.ft.	129	62	60	25	52	...	328
9. Teak wood battened door complete as per specification.	S.ft.	36	54	54	30	36	24	234
10. Teak wood battened windows with iron bars complete as per specification.	„	...	10	...	18	16	12	56

Items of work	Unit	Traffic quarters at Agasanahadlu	Traffic quarters at Narasimharajapura	Traffic quarters at Tadasa	Menials quarters at Tadasa	Menials quarters at Narasimharajapura	Menials quarters at Duggalapura	Total quantity
11. Teak-wood battened ventilators with iron bars complete as per specification.	S.ft.	...	18	18	...	...	...	36
12. Teak-wood cupboards complete including cross planks as per specification.	„	10	...	...	...	...	...	10
13. Teak-wood wrought and put up including wood oiling, 2 coats.	C.ft.	12·00	11·84	13·00	14·00	23·60	17·00	91·44
14. Roofing with 1st Class Mangalore tiles on 2" x 1" teak-wood reepers including wood oiling, chunam borders and wind ties fixed complete with R. M. C. for tile consignment.	S.qr.	1·90	3·00	3·65	4·27	7·41	3·76	23·99
15. Ridge tiles set in mortar ...	R.ft.	17	25	32	23	26	54	177
16. Preparing valley complete with G. I. sheet and planking, etc. as per specification.	„	18	9	10	...	...	...	37
17. Labour charges for fixing G. I. sheet complete (sheets and bolts will be supplied by Dept).	Sq.	4·88	2·20	0·90	...	...	...	7·98
18. Flooring with 3" concrete and cement plastering ½" thick as per specification.	„	0·80	1·44	1·47	2·15	3·63	1·35	10·84
19. Plastering with mortar ...	„	7·25	15·26	11·70	14·0	26·0	11·0	85·21
20. White and color washing, 2 coats.	„	...	...	11·70	14·0	26·0	11·0	62·70
21. Removing the existing roof and re-roofing with the same materials.	„	4·40	...	...	...	...	...	4·40
22. Coping burnt brick in mortar and chunam plastering complete.	R.ft.	...	19	19	...	...	...	38
23. Painting doors and windows with silicate.	Sq.	...	...	...	1·10	2·20	0·83	4·13
24. Providing pestle and mortar.	Each	...	...	...	1	...	...	1
25. Do sinks and oven ...	„	...	...	...	...	1	1	2
26. Do planks one inch thick for shelves.	S.ft	...	...	...	...	5	...	5
27. Do coat racks ...	Each	..	...	...	...	2	...	2
28. Do masonry drain 6".	R.ft.	...	...	...	...	40	...	40
29. Do teak-wood eave boards plain.	„	...	...	..	..	...	74	74
30. Do teak-wood finials big.	Each	...	...	...	...	...	2	2
31. Do teak-wood finials small.	„	...	...	...	...	...	6	6

N. B.—Work should be done strictly according to the correct specification.

D. V. NARASIMHA RAO,
Executive Engineer,

HASSAN DIVISION.

Abstract Notification dated 10th August 1933.

The attention of the public is invited to the detailed notification calling for tenders for Repairing and Constructing two sluices to Dudda Doddakere Regd. No. 1808 of Hassan Taluk, published in pages 1024 to 1026, Part VI of the *Mysore Gazette*, dated 17th August 1933.